

**TENDER SCHEDULE
KERALA HAJ COMMITTEE**

Name of Work : - Providing Yard light in Hajj House, Airport road, Karipoor in connection with Hajj Camp 2013.

PAC □: 1,33,646/-

EMD □ 3,350/-

Period of completion : 15 days

Due Date:

Cost of Tender Schedule : □. 400.00 + Vat

Sl.no	Qty	Particulars	Rate	Rate per unit in words	Unit	Amount
1	1 Nos	Supply and erection of octogonal galvanized pole 7mtr height complete with out arm suitable size base plate , space for mounting control switch box with inspection type door at a height of 550mm from the road level including Bakelite sheet with 10A FP MCB & Stud terminals etc as required.	19160.00	(Rupees Nineteen thousand one hundred and sixty only)	Each	19160.00
2	1 Set	Supply 4Nos suitable size foundation bolt with temp. plate etc as required.	1951.00	(Rupees One thousand nine hundred and fifty one only)	Set	1951.00
3	0.5 m3	Earth work excavation in ordinary soil and depositing with a lead up to 50 m and lift up to 1.50 m including neat banking	95.00	(Rupees Ninety five only)	m3	47.50
4	0.75 m3	Cement concrete 1:2:4 using 20mm (nominal size) broken stone for reinforced concrete work.	5822.00	(Rupees Five thousand eight hundred and twenty two only)	m3	4366.50
5	1 m2	Plastering with cement mortar 1:4, 12mm thick one coat.	165.00	(Rupees One hundred and sixty five only)	m2	165.00
6	6 Nos	Supply, conveyance, installation, testing and commissioning of single piece 250 W MH Asymetrical Non integral flood light luminaire suitable for high mast installation with die-cast aluminium housing with top opening in powder coated finish with POT optics reflector, toughened glass cover (IP 66 protection) control gear and lamp holder suitable for the following types of lamps pre-wired up to the terminal block including supply and providing suitable lamps in the existing head frame and giving connections with the extended original wiring and giving connection etc. as required	10840.00	(Rupees Ten thousand eight hundred and forty only)	Each	65040.00
7	5 Kg	Supplying and installation of supports , anchor bolts etc made out of suitable size single section MS angle, flats etc as required including painting with 2 coats of synthetic enamel paint (<i>for supporting clamp for flood light luminaries</i>)	71.00	(Rupees Seventy one only)	Kg	355.00
8		Supply and drawing the following sizes of multi-core PVC insulated & PVC sheathed 650/1100 V grade copper conductor round flexible cables conforming to IS 694 part I 1960 in the existing surface / recess conduit as required including giving necessary connections of the following sizes.				
a	50 Mtr	3 core 1.50 sq. mm.	72.00	(Rupees Seventy two only)	Mtr	3600.00
9		Supply & laying of one number PVC insulated and PVC sheathed armoured aluminium power cable of 1.1KV grade of the following sizes in the existing RCC/ HUME / STONE WARE/ GI/ DWC pipe as required.				

TENDER SCHEDULE
KERALA HAJ COMMITTEE

Name of Work : - Providing Yard light in Hajj House, Airport road, Karipoor in connection with Hajj Camp 2013.

a	30 Mts	4 core 10 sq mm	181.00 (Rupees One hundred and eighty one only)	Mtr	5430.00
10		Supply, laying and clamping of 1 no. PVC insulated and PVC sheathed armoured aluminium power cable, 1.1 KV grade of the following sizes using clamps noted along with the cables, spacing of clamps not exceeding 60cms, making good the damages , colour washing etc. as required.			
a	30 Mts	4 core 10 sq mm with factory made clamp	200.00 (Rupees Two hundred only)	Mtr	6000.00
11		Supplying siemens / tropodur type nickel plated single compression brass cable gland for PVC insulated and PVC sheathed armoured aluminium/ copper conductor cable 1.1 KV grade, and making end termination suitable for 2/ 3/ 3½/ 4 core cable of the following sizes as required.			
a	4 Nos	10 sq mm	112.00 (Rupees One hundred and twelve only)	Nos	448.00
12		Supplying and providing earth clamps for siemens/ tropodur type cable glands of suitable length and other dimensions noted along with each size of glands for the following sizes of cables as required.			
a	4 Nos	10 sq mm with 12 mm wide x 1 mm thick clip	15.00 (Rupees fifteen only)	Nos	60.00
13		Supply of superior quality aluminium tubular cable socket and making core termination of cables of the following sizes including crimping etc. as required.			
a	16 Nos	10 sq mm	10.00 (Rupees Ten only)	Nos	160.00
14		Supplying, laying and jointing of the following sizes of double wall corrugated (DWC) pipes made out of HDPE conforming to IS 14930 Part II for mechanical protection to underground power cables with all required accessories in ground in the existing trench			
a	25 Mtr	50 / 38 mm or nearest size	120.00 (Rupees One hundred and Twenty only)	Mtr	3000.00
15		Supply and clamping the following sizes of PVC pipe on wall with all required accessories including cutting and making good the walls, colour washing etc. as required as protective covering to cables.			
a	5 Mtr	32 mm dia PVC pipe (8 Kgf / cm²)	58.00 (Rupees Fifty eight only)	Mtr	290.00
16		Supply and installation of the following accessories suitable for 50 Hz AC supply conforming to IS 8828-1995/ IEC 60898 of the following current ratings in the existing enclosure and giving connections as required			
a	12 Nos	10 way single phase double cover (IP 42/43)	(Rupees One thousand five hundred and seventy 1571.00 one only)	Each	18852.00
17		Supply and installation of the following accessories suitable for 50 Hz AC supply conforming to IS 8828-1995/ IEC 60898 of the following current ratings in the existing enclosure and giving connections as required			
a	1 Nos	40 A four pole mini break isolator	748.00 (Rupees Seven hundred and forty eight only)	Each	748.00
b	3 Nos	6 A to 32 A, 10 kA, DP MCB (B curve)	531.00 (Rupees Five hundred and thirty one only)	Each	1593.00
18		Supply and drawing bare earthing conductors of the following sizes along with wiring/ cables and giving connection as required.			
a	60 Mtr	2.65 mm copper conductor (12 SWG) (through cable)	38.00 (Rupees Thirty eight only)	Mtr	2280.00

**TENDER SCHEDULE
KERALA HAJ COMMITTEE**

Name of Work : - Providing Yard light in Hajj House, Airport road, Karipoor in connection with Hajj Camp 2013.

19	supply of superior quality copper earth socket for the following sizes of earth conductor including crimping etc. as required.			
a	4 Nos 2.65 mm (12 SWG)	16.00 (Rupees Sixteen only)	Each	64.00
20	Supply and providing the following sizes of bolt and nut with washers on the existing MS box / earth bus etc. as required including drilling necessary holes as required			
a	4 Nos 12 x 3 mm brass bolt & nut	9.00 (Rupees Nine only)	Each	36.00
				Total 133646.00

I/We Sri.....is/ are hereby Agree to execute the work at% above /below/ estimate rate less costs of departmental materials specified to be supplied.

FOR OFFICE USE ONLY

- | | | |
|---|---|---|
| 1 | Scorings. | : |
| 2 | Overwriting | : |
| 3 | Correctons | : |
| 4 | Insertions | : |
| 5 | Rate quoted by the contractor | : |
| 6 | Dated signature and designation of the office opening tender. | : |